Item	Dimensions			Description	Quantity	Unit	Rate	£ p
				D GROUNDWORK				
				D20 Excavating and Filling				
				Excavating topsoil for preservation				
A				Average depth 150mm	8843	m2	1.74	15386.82
		23.300 6.000	139.800	Main Access				
	2/3/	55.450 23.890	7948.203					
		33.000 2.000	66.000					
		16.000 23.500	376.000					
		21.000 4.800	-100.800	ddt existing hardstanding				
		16.000 5.000	-80.000					
	1+2+1/	22.000 3.000	264.000					
	½/	55.000 6.000	165.000					
	¼/	14.000 2.000	7.000					
		2.000 3.000	6.000					
		9.300 5.600	52.080					
				Excavating to reduce levels				
B				Maximum depth not exceeding 1.00m ; Commencing at ground level	1952	m3	2.08	4060.16
		23.000 6.000 0.500	69.000					
		88.000 59.000 0.250	1298.000					
		26.000 45.000 0.500	585.000					
				E IN SITU CONCRETE/LARGE PRECAST CONCRETE				
				E05 In situ concrete construction generally				
				Plain Concrete				
				Concrete C20; ordinary portland cement; 20mm aggregate				
				Beds				
C				Thickness 150-450mm ; Sloping not exceeding 15 degrees ; Poured on or against earth or unblinded hardcore	126	m3	90.68	11425.68
				F MASONRY				
				F10 Brick/Block walling				
				Facing bricks London Brick Spec. 1275/4; in readymixed coloured mortar 1:3				
				Walls ; stretcher bond				
D				103mm thick ; facework one side; pointed ; Vertical	475	m2	50.09	23792.75