Item	Description	Quantity	Unit	Rate	£ p
	D GROUNDWORK				
	D20 Excavating and Filling				
	Excavating topsoil for preservation				
A	Average depth 150mm	8843	m2	1.74	15386.82
	Excavating to reduce levels				
B	Maximum depth not exceeding 1.00m ; Commencing at ground level	1952	m3	2.08	4060.16
	E IN SITU CONCRETE/LARGE PRECAST CONCRETE				
	E05 In situ concrete construction generally				
	Plain Concrete				
	Concrete C20; ordinary portland cement; 20mm aggregate				
	Beds				
C	Thickness 150-450mm ; Sloping not exceeding 15 degrees ; Poured on or against earth or unblinded hardcore	126	m3	90.68	11425.68
	F MASONRY				
	F10 Brick/Block walling				
	Facing bricks London Brick Spec. 1275/4; in readymixed coloured mortar 1:3				
	Walls ; stretcher bond				
D	103mm thick ; facework one side; pointed ; Vertical	475	m2	50.09	23792.75
	G STRUCTURAL/CARCASSING METAL/TIMBER				
	G20 Carpentry/Timber framing/First fixing				
	Sawn Softwood				
	Wall or partiton members				
E	50 x 100mm	55	m	3.05	167.75

To Collection 54833.16